

**RESOLUTION NO. 14-2025**

Introduced by Matt Grieves

**A RESOLUTION AUTHORIZING THE CITY MANAGER TO ACCEPT THE PROPOSAL AND ENTER INTO AN AGREEMENT WITH FIRELANDS ELECTRIC, INC. FOR THE INSTALLATION OF TWO (2) SECTIONALIZERS AND RELATED CONDUIT, ONE ON RYE BEACH ROAD AND ONE ON THE SOUTH SIDE OF SAWMILL PARKWAY, RELATING TO THE HURON PUBLIC POWER EXPANSION PROJECT IN AN AMOUNT NOT TO EXCEED FIFTY-FIVE THOUSAND NINE HUNDRED SIXTY AND XX/100 DOLLARS (\$55,960.00).**

**BE IT RESOLVED BY THE COUNCIL OF THE CITY OF HURON, OHIO:**

**SECTION 1.** That the City Manager shall be, and he hereby is, authorized and directed to accept the proposal and enter into an agreement with Firelands Electric, Inc. for the installation of two (2) sectionalizers and related conduit, one on Rye Beach Road and one on the south side of Sawmill Parkway, relating to the Huron Public Power Expansion Project in an amount not to exceed Fifty-Five Thousand Nine Hundred Sixty and xx/100 Dollars (\$55,960.00). A copy of the proposal is attached hereto as Exhibit A and incorporated herein by reference.

**SECTION 2.** That this Council hereby finds and determines that all formal actions relative to the adoption of this Resolution were taken in an open meeting of this Council and that all deliberations of this Council and of its Committees, if any, which resulted in formal action, were taken in meetings open to the public in full compliance with applicable legal requirements, including O.R.C. §121.22.

**SECTION 3.** That this Resolution shall be in full force and effect from and immediately after its adoption.

ATTEST:

  
Clerk of Council

ADOPTED:

28 JAN 2025

  
Monty Tapp, Mayor

# FIRELANDS ELECTRIC, INC.

OH Lic #19787

"A Drug Free and OSHA Trained Company"

2721 Columbus Ave.  
Sandusky, Ohio 44870  
PH: 419-626-4908  
FX: 419-626-4397

## Quote #324-5211

To: Huron Public Power	Date: 11/18/2024
	Re: 2 Sectionalizers
Phone: 419-602-0503	ATTN: Mike Spacek

Firelands Electric, Inc. proposes to furnish labor, materials, and equipment to complete the following scope of work:

1. Includes the labor and materials to set 2 sectionalizers and run a pair of 4" PVC schedule 40 conduit from the sectionalizer SC1 that will be in place at Rye Beach to the one we are setting on the south side of Sawmill Parkway SC3. We also run a pair of 4" conduit from the south sectionalizer SC3 to the north side of the road where we will be setting another sectionalizer SC4. We will subcontract an excavation company to dig out for a designated area for a sectionalizer SC1 box at the corner of Rye Beach Road and Sawmill Parkway. Out of that box, we will run 2 4" schedule 40 PVC conduit to the location of the sectionalizer box located approximately 450' down Sawmill Parkway. This sectionalizer will be located on the south side of the road. We will utilize the existing 2 4" conduit running under the driveway of the trucking company. We will connect our conduit to the existing conduit to complete the run. Also, out of the Sawmill Parkway sectionalizer SC3, we will connect to the 2 4" conduit running under Sawmill Parkway to the north. We will use those conduits to run to the sectionalizer SC4 we are setting for the Paper Resources project. We will pull 3 4/0 15kv 133% Insulation Aluminum Jacketed 113 Concentric Neutral cables from the Rye Beach Road sectionalizer SC1 to the Sawmill Parkway sectionalizer SC3. and Next we will pull 1/0 15kv 133% Aluminum Jacketed Concentric Neutrals across the street to the Paper Resources sectionalizer SC4. The second conduit in each run shall be a spare. We will install 200-amp load break 90s on both ends of each cable.
2. Includes 4" PVC 90 stubs for future in each sectionalizer box. 2 east and west per the drawing.
3. Includes all 4" conduit to have 3' of fill above the top of each conduit.
4. Includes the use of a metallic buried line warning tape 1' below grade.
5. Includes grounding per the drawing supplied by HPP.
6. Excludes the planting of grass seed or landscaping repairs.
7. If there are not 2 conduits crossing the driveway area, there will be an additional 175' of excavation plus conduit and labor. This will be an additional \$9,225.00. This does not include any potential boring of conduit under Sawmill Parkway.
8. Includes sales tax.
9. Includes permit fee.

**NOTE:** not included- charges from Ohio Edison/ First Energy if any. Labeling of circuits which are currently not labeled. Repair circuits not working before installation. Repair or replacement of any unmarked utility lines. We request an eight-hour working window, during normal working hours; some projects may be completed earlier.

**The Electrical Base Bid for "2 Sectionalizers" \$46,735.00 or \$55,960.00**

**Please be aware that commodity prices are constantly changing and may affect the final estimate, and we are experiencing material shortages that may delay the project's completion. We thank you for your patience.**

We propose hereby to provide material and labor - complete as stated above, for a sum of \$47,735.00 or \$56,960.00.

*John Young*  
Authorized by John Young

\*\*\*\* Proposal is Valid for 30 Days \*\*\*\*

---

Acceptance of Proposal - The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. *Payment terms. - 50% prior to commencement of project, with 50 % balance due at time of project completion to avoid interest & collection fees.*

Date: 01/29/2025

Signature: 